

LiveWest Repairs
Purchase Order

Page 1 of 3

Order No. CN011041

Date of order 08/07/2025

To:
BPM Contracting Services Ltd
12 Stable Yard
Bath
BA2 3AY

Delivery Address:
39 Sidford Road
Bedminster
Bristol

BS3 5DN

Invoice Address:
LiveWest Homes Limited
1 Wellington Way
Skypark
Clyst Honiton
Exeter

Contact:
Shelby Bowman
Phone:
Fax:

Date due:

Job ID: UR0771283

Additional Instructions:

Code	Supplier	Description	Qty	Unit	VAT %	Unit Cost	Order Value

**LiveWest Repairs
Purchase Order**

Page 2 of 3

D20		<p>ROOFING - Provide a scaffolding to allow access to the roof along the damaged roof from vehicle impact . The scaffold will need to run along the whole elevation to the right side of the property. end elevation. Please advise of the cost for this scaffold for insurance purpose. BE ASBESTOS AWARE 1.00 0.0000 To supply, install and maintain TG20 Compliant scaffolding to the side elevation of the property sufficient to allow safe working access to the roof and wall elements of the structure affected by the vehicle impact. Working lifts to be fully boarded with toe and hand rails with no ladder access to the ground Lower tubes to be foam wrapped and lit adjacent to road with warning signs for passing traffic and safety kerbing to protect outer corner of scaffold 1.00 1685.0000 To remove verge/barge board to front elevation of roof up to ridge. Remove dry verge, verge tiles and 2 rows in full length. Cut back battens and felt to expose roof rafters and wall plates. Carry out localised timber repairs to ladder rafter and noggins etc. Refix wall plates if loose. Renew dryverge capping and reuse as much of the grey PVC cladding as possible. Renew soffit, fascia and box section of pvc cladding. Renew section of guttering and downpipe. Resecure end ridge tiles x 2. Hack off and patch k-render to 1sqm patch at top of apex. Apply new mastic where is split. Minimum 3 days 2 ops materials £100. 1.00 0.0000 209001 Verge:Renew dry or cloaked verge complete, remove/refix tiles as necessary, remove existing, fix new dry or cloaked verge and half tile, end stops, jointing pieces, ridge end units, make good. 8.00 285.8400 209005</p>	1.00	NO	20.00	3,254.36	3,254.36
-----	--	--	------	----	-------	----------	----------

**LiveWest Repairs
Purchase Order**

Page 3 of 3

		<p>Verge:Renew or refix dry verge ridge end or end stop. 2.00 22.1200 201309 Roof Tile:Remove and refix loose plain concrete or clay roof tiles (in groups over 10 No.). 4.00 313.5200 201150 Roof Covering:Extra over any renewal or refixing of roof tiles or slates for renew roofing felt and battens. 8.00 227.2000 Net Estimate Total: £3254.36 VAT Estimate Total: £650.87 Gross Estimate Total: £3905.23</p>					
Signed on behalf of LiveWest :					Nett Order Value		3,254.36
					VAT		650.87
					Gross Order Value		3,905.23

Please refer to our standard terms and conditions at <https://www.livewest.co.uk/about-us/tenders-and-suppliers>