

Customer:
BPM Contracting Services Ltd
Unit 12, Stable Yard
Windsor Bridge,
Bath
BA2 3AY

Site:
7 Fountain Buildings
Bath
BA1 5DU

Date: 30/07/25

Quote No: SN42545

Our Ref:

For the attention of

Dear Sirs,

We have pleasure in submitting the following Quotation for the hire, delivery, erection, dismantling and clearing away on completion of scaffold. This complete Quotation is subject to the Trading and Safety Conditions on the reverse hereof.

Yours faithfully, for **SN SCAFFOLD**

Item No: 1

SPECIFICATION

THE PAVEMENT LICENCE COST IS £1115 + VAT PER EVERY 28 DAYS
THIS IS EXTRA TO THE COST BELOW

Independent physically tied scaffolding to give access for roof repairs to the following external elevation(s).
(Excluding any adaption). Built in 2.00m high lifts, as follows :-

Front Elevation

2.40m x 5 No lifts high, **with the top lifts boarded - with inside boards to suit - boarded out to the middle of the dormer window - with longer end guardrails**

Complete with 1 No Gin Wheel(s) & Rope(s).

With Foam Protection To The Standards

Board Detail (5 main deck, 1 inside & 1 toe board(s) per fleet)

With one lift of boards, placed by us on the top lift once only, **and a double layer of boards complete with a polythene insert as protection on the base lift.**

The protection lifts of boards should remain in the set position at all times.

SN SCAFFOLDS

Customer: BPM Contracting Services Ltd

Site: 7 Fountain Buildings, Bath, BA1 5DU

Page No: 2
Quote No: SN42545
Date: 30/07/25

SPECIFICATION

Item No: 1 continued...

Ladder Access

Ladder access built within the scaffold in one position, from the base lift, to the full height, with pole ladders fixed at the rake, including appropriate boarded landings.

Loading

The specified scaffold(s) will be constructed on a nominal 2.10m x 1.24m grid and will support one number working (decked) lift with a load of 2.00 kN per metre square. A further working (decked) lift will support a load of 1.0 kN per metre square. The working decking on the inside line of the scaffold will support a load of 0.75 kN per metre square. These loads to be uniformly distributed and must not be exceeded.

Price Details

Contract Price **£860.00** (All prices subject to VAT)

Hire Period 4 Week(s) (Irrespective of completion in that time)

Extended Hire £00.00 Tubular Materials
£00.00 Scaffold Boards } per week or part thereof, pro rata to amount standing.

Daywork covering minor alterations to existing scaffolds only will be charged at £40.00 per man hour, plus expenses necessarily incurred.

a) We to obtain the requisite licence before we commence work, and we must reserve the right to revise our quotation if such licence imposes conditions which involve additional expense to us. (e.g. necessitating working out of normal hours or to provide a protection fan etc.,). Client to provide, maintain and remove suitable lighting and any signs required by the Local Authority, for the duration that the scaffold is standing.

b) Should the site conditions demand a bulk timber fender or the like - set in the kerb, then this to be provided, placed and removed by you.

Main contractor to obtain permission for us to have access to or erect from and/or over adjoining property.

Our price is based on understanding that we will have good means of ingress and egress for our men and materials to all parts of the site.

Client to ensure Security of the scaffold(s) at all times, and prevent Unauthorized access to same.

a) The Local Authority now impose a fee and require seven days notice prior to issuing a licence to erect a scaffold on or over a public high way.

b) Should you require us to obtain the permit on your behalf there will be a charge of £115 per every 28 days added to your account.