

**Customer:**

Curo,  
The Maltings,  
River Place,  
Lower Bristol Rd,  
Bath.

**Site:**

Claude House  
Claude Avenue  
Bath  
BA2 1AB

**Date:** 14/07/25**Quote No:** SN42491**Our Ref:****For the attention of**

Dear Sirs,

We have pleasure in submitting the following Quotation for the hire, delivery, erection, dismantling and clearing away on completion of scaffold. This complete Quotation is subject to the Trading and Safety Conditions on the reverse hereof.

Yours faithfully, for **SN SCAFFOLD**

**Item No:** 1**SPECIFICATION**

Independent physically tied scaffolding to give access for roof repairs to the following external elevation(s). (Excluding any adaption). Built in 2.00m high lifts, as follows :-

**Right Hand Elevation**

2.40m x 3 No lifts high, **3 + 1-2 boards wide - with the top lift boarded**

**Complete with 1 No Gin Wheel(s) & Rope(s)****With Foam Protection To The Standards****Board Detail** (5 main deck, 1 inside & 1 toe board(s) per fleet)

With 1 No lift of boards, placed once only by us.

**Ladder Access**

Ladder access built within the scaffold in one position, from the ground, to the full height, with pole ladders fixed at the rake.

# SN SCAFFOLDS

**Customer:** Curo,, The Maltings,, River Place,

**Site:** Claude House, Claude Avenue, Bath, BA2 1AB

**Page No:** 2  
**Quote No:** SN42491  
**Date:** 14/07/25

## SPECIFICATION

**Item No:** 1 continued...

### Loading

The specified scaffold(s) will be constructed on a nominal 2.10m x 1.24m grid and will support one number working (decked) lift with a load of 2.00 kN per metre square. A further working (decked) lift will support a load of 1.0 kN per metre square. The working decking on the inside line of the scaffold will support a load of 0.75 kN per metre square. These loads to be uniformly distributed and must not be exceeded.

## Price Details

**Contract Price** £575.00 (All prices subject to VAT)

**Hire Period** 4 Week(s) (Irrespective of completion in that time)

<b>Extended Hire</b>	£00.00	Tubular Materials	} per week or part thereof, pro rata to amount standing.
	£00.00	Scaffold Boards	

**Daywork** covering minor alterations to existing scaffolds only will be charged at £40.00 per man hour, plus expenses necessarily incurred.

*a. In order to comply with Construction Regulations and TG20:08, the scaffold must be tied to the permanent structure at the recommended intervals.*

*b. As "Hilti ties" or similar anchors are to be used into the fabric of the building, it will be your responsibility to obtain or give permission for the holes to be drilled into the fabric of the building.*

*c. We will carry out the drilling of 20mm dia. holes 85mm deep in the face of the building at the recommended centres and fixing, but confirmation that permission has been obtained and necessary advice regarding location of the ties must be received in writing before we proceed.*

*d. We can accept no responsibility whatsoever for damage to the building or consequential costs arising as a result of fixing or use of "Hilti ties" or similar anchorages.*

*e. Making good at all times to be carried out by the Main Contractor.*

*Although we will take every possible care, we regret that we cannot accept responsibility for damage caused by or arising out of working off the garden. Any pruning etc., to be carried out before we commence erection.*

*Our price is based on understanding that we will have good means of ingress and egress for our men and materials to all parts of the site.*

*Client to ensure Security of the scaffold(s) at all times, and prevent Unauthorized access to same.*