

Customer:
BPM Contracting Services Ltd
Unit 12, Stable Yard
Windsor Bridge,
Bath
BA2 3AY

Site:
Mcintyre House
Forest Road
Kingswood
Bristol
BS15 8FT

Date: 13/05/25

Quote No: SN42326

Our Ref:

For the attention of

Dear Sirs,

We have pleasure in submitting the following Quotation for the hire, delivery, erection, dismantling and clearing away on completion of scaffold. This complete Quotation is subject to the Trading and Safety Conditions on the reverse hereof.

Yours faithfully, for **SN SCAFFOLD**

Item No: 1

SPECIFICATION

MUST LEAVE GOOD / CLEAR ACCESS UP / DOWN STAIRCASE

Independent physically tied scaffolding to give access for general repairs to the following external elevation(s). (Excluding any adaption). Built in 2.00m high lifts, as follows :-

Internal Staircase

1.00m x 3.00m on plan x 1 - 2 No lifts high, **boarded - built off the top flight of stairs / landing**

With Foam Protection To The Standards

Board Detail (5 main deck, 1 inside & 1 toe board(s) per fleet)

With 1 No lift of boards, placed once only by us.

Excluding Ladders

Loading

The specified scaffold(s) will be constructed on a nominal 2.10m x 1.24m grid and will support one number

SN SCAFFOLDS

Customer: BPM Contracting Services Ltd

Site: McIntyre House, Forest Road, Kingswood, Bristol

Page No: 2
Quote No: SN42326
Date: 13/05/25

SPECIFICATION

Item No: 1 continued...

working (decked) lift with a load of 0.75 kN per metre square. A further working (decked) lift will support a load of 0.375 kN per metre square. These loads to be uniformly distributed and must not be exceeded.

Price Details

Contract Price **£575.00** (All prices subject to VAT)

Hire Period 4 Week(s) (Irrespective of completion in that time)

Extended Hire	£00.00	Tubular Materials	} per week or part thereof, pro rata to amount standing.
	£00.00	Scaffold Boards	

Daywork covering minor alterations to existing scaffolds only will be charged at £40.00 per man hour, plus expenses necessarily incurred.

Our price is based on understanding that we will have good means of ingress and egress for our men and materials to all parts of the site.

Client to ensure Security of the scaffold(s) at all times, and prevent Unauthorized access to same.

Because of the very nature of the work, it is necessary for us to carry our materials through the building - whether occupied or not. Whilst we will take all possible care, we would point out that we cannot be held responsible for damage or any resulting costs.

Our offer is based on the understanding that we will have good access at ground level for our men and material to the vessel and/or structure interior.

Due to the long carry on this job, is reflected in our price due to the higher amount of labour time required to carry out this work.